

1. The cost for dirt haul-off should be included in the bid, or the owner may coordinate with the contractor to discuss finding a place for the excess dirt on site.
2. The pipe cannot be placed under pavement due to cover limitations. We recommend including tree removal as a part of the bid.
3. Recommend using Downspout Boots see links below;

<https://jrroe.com/downspoutboots.html>

https://groupnei.com/product_category/downspout-boots/

4. We are required to show DIP due to cover limitations.
5. Tapestry may relocate/remove all rain barrels, flower boxes, picnic tables, etc. but please include this within your quote clearly identified.
6. Yes, Tapestry can have their HVAC contractor disconnect, remove, and reinstall the HVAC units within the working area during construction but the contractor will need to coordinate the work.
7. A brick manhole structure should be acceptable.
8. The intent is to remove all existing above ground pipes along buildings and all roof drains will tie into new pipes. We have not finalized the Demolition Plans yet, but this adjustment will be made